# BENGALURU CENTRAL CITY CORPORATION

**No: EE(SJN)/e-Proc/QTN/06/2025-26**

**Office of the Executive Engineer**
**Shivajinagara Division,**
**Thimmaiah Road, Queens Road**
**Bangalore - 560001**
**Date: 10-12-2025**

**Short Term Quotation Notification For Rates**

The Quotation are invited by the undersigned on behalf of the Commissioner / Zonal Commissioner, BCCC from the Reputed agencies / Suppliers / Distributors / Contractor for the work of **Supply, Casting, Erection and Fixing of Dr B R Ambedkar Statue in Shivajinagara Division**. The Interested supplier / agencies are requested to Submit / Upload their quotation Through https://kppp.karnataka.gov.in/. on or before 18-12-2025 at 4:00 pm as details in the table indicated below, the quotation shall be opened on 19-12-2025 at 4:30 pm

| Sl No | Particulars | Unit | Qty |
|---|---|---|---|
| 01 | SITC of Works Contract of Custom Artist Designed Statue made of broze material featuring Dr.B R.Ambedkar bust size statue as per approved design. The statue will be 2.5' tall (and proportionate width) with average thickness of 12 to 16 mm bronze sheet from ground which includes the base at Pedestal area. The unit will be mounted to pedestal area.. , including cost of all materials, making clay model, making mould, making fibre glass statue, making plaster of parris piece mould, making wax statue, bronze casting, welding of bronze statue in foundry, bracing with steel flats with nut & bolts for structural stability, transportation, hoisting parts on to pedestal, welding steel structure and bronze parts together,final finishing and painting, installation on pedestal at site i.e work spot, including all Artists,skilled and unskilled labour, hiring of machineries, transportation and all other incidental charges for successful completion of work in coordination with civil works, includes the certificates to be obtained from the Quality assurance authorities etc. complete as per the directions of Engineer-in-charge of work. (Quotation Rate Excluding GST) | Unit | 1 |
| 02 | SITC of Works Contract of Custom Artist Designed Anamorphic Perspective Metal Art Installation featuring the appearance of Dr. Ambedkar's face to be formed when viewed from specific vantage point or viewing area. When viewed from generic angle will look like a line of vertical louvers with abstarct shapes at different points of the vertical louvers. The entire art installation will be made of vertical MS Square pipes 2" x 2" with necessary base, top covering treatment, anchoring to floor base plate and the abstract shapes to | Unit | 1 |

| | | | |
|---|---|---|---|
| | be made of MS metal 3mm thick MS metal sheet. The metal pipe and abstract shapes as per perspective design will be firmly embedded on the each of the vertical pipe. The entire art installation will be 10'w x 10' h. The MS metal units will be treated for anti-corrosion and powder coated / painted in black colour as per the design. The floor area of the installation surface will feature metal base plate 10mm thick rectanglar in shape (basedon CG load)which will hold the array of the vertical louvers approx 24 nos. The base plate will be mounted to the floor area with required nuts and bolts. The installation is to viewed from a minimum distance of 50' away from the art installation to see the abstract shapes forming into the face of Dr. Ambedkar the rate quoted is including cost of all materials, transportation, hoisting parts, welding steel structure, final finishing and painting, installation at work spot, including all Artists, skilled and unskilled labour, hiring of machineries, transportation and all other incidental charges for successful completion of work in coordination with civil works, includes the certificates to be obtained from the Quality assurance authorities etc. complete as per the directions of Engineer-in-charge of work. Custom Artist Designed Anamorphic Perspective Metal Art Installation of Dr. Ambedkar's face (Quotation Rate Excluding GST) | | |
| 03 | SITC of Works Contract of Custom Artist Designed Preamble of Constitution of India will be made larger than life size measuring 10' x 15' and will be mounted on the custom created backwall which will feature in 2 different languages - Content Styling, designing in English and Kannada. The Ornamental boundary design along four sides of the constitution of India will be custom designed and fabricated in 2mm MS Metal Sheet, laser engraved / cut as per design and will glow from behind to give a glow effect in the evening based on the ligthting design and fixtures mentioned in the lighting works. The metal will be treated for anti-corrosion and suitable paint treatment as per the final approved design. Both the language art works will be mounted on the wall area behind the site border facing the traffic junction signal. The text and font will be designed suitable for reading from a minimum distance of 15-20 feet from the wall. The unit will have frame structure designed to mount on to the wall and designed to accomodate lighting design from behind. Warranty 1 year.Custom Artist Designed Preamble of Constitution of India (Quotation Rate Excluding GST) | Unit | 2 |
| 04 | SITC of Works Contract of Custom Artist Designed Great Visionary Leaders of India featuring Pandit Jawaharlal Nehru, Mahatma Gandhi, Maulana Azad measuring 1 mtr x 1 mtr and will be mounted on the custom created backwall which will feature their facial expression with key message in quotes in English - Content Styling, designing in English. The art sculpture will be custom designed and fabricated in 2mm SS Metal Sheet, laser engraved / cut as per design and will glow from behind to give a glow effect in the evening based on the ligthting design and fixtures mentioned in the lighting works. The metal will be treated for anti-corrosion and suitable paint treatment as per the final approved design. All the art works will be mounted on the wall area behind the site border facing the traffic junction signal. The text and font will be designed suitable for reading from a minimum distance of 15-20 feet from the wall. The unit will have frame structure designed to mount on to the wall and designed to accomodate lighting design from behind. Warranty 1 year.Custom Artist Designed Great Visionary Leaders of India (Quotation Rate Excluding GST) | Unit | 3 |
| 05 | SITC of Works Contract of Custom Artist Designed Dedication board featuring the MLA initiative spl works. The unit will be custom shape | Unit | 1 |

| | | | |
|---|---|---|---|
| | measuring 2' x 4' as per approved design - Content Styling, designing in English & Kannada. The art sculpture will be custom designed and fabricated in 2mm SS Metal Sheet, laser engraved / cut as per design and will glow from behind to give a glow effect in the evening based on the ligthting design and fixtures mentioned in the lighting works. The metal will be treated for anti-corrosion and suitable paint treatment as per the final approved design. All the art works will be mounted in the front area before the assembly theme structure facing the traffic signal. The text and font will be designed suitable for reading from a minimum distance of 6 feet from the installation. The unit will have mounting units to firm with the floor area with suitable foundation nuts & bolts firmly tightened and designed to accomodate lighting design. Warranty 1 year. Custom Artist Designed Key Message Board by MLA (Quotation Rate Excluding GST) | | |
| 06 | DIGITAL TIMER - Automatic Digital Timer Switch DIN Rail Mounted Type, input 180-250V, internal battery to retain programming schedule even in case of power failure, Working Voltage: Ac220v/50hz /Working Temperature: - 20℃~ 60℃ / Switch Capacity: 16 Ampere / Programmable Number:16 Programs / Day / Timing Error :≤2 Seconds Per Day / Consumption PowerConsumption:≤5w / Battery Cell : Rechargeable Battery (Quotation Rate Excluding GST) | Nos | 2 |
| 07 | SITC of architectural lighting for Dr. Ambedkar Bronze statue (as per approved designs) Statue lighting to cover statue of 2.5' wide bust size (golden colour), 15º/25º beam angles, 12-15W or as recommended, 3000K, IP65, mounting accessories for max safety. Colour: Grey / Black. Warranty 1 year. (Quotation Rate Excluding GST) | Nos | 6 |
| 08 | SITC of architectural lighting for installation white backwall (as perapproved designs) High quality 1 mtrs wide Wall Washers lights , Power: 100W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 45º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year. (Quotation Rate Excluding GST) | Nos | 30 |
| 09 | SITC of architectural lighting for installation white high backwall (as perapproved designs) High quality spot lights , Power: 15W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 15º/30º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year. (Quotation Rate Excluding GST) | Nos | 30 |
| 10 | SITC of architectural lighting for Floor Area (as perapproved designs) High quality floor mounted spot lights , Power: 0.5W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 5º/10º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year.(Quotation Rate Excluding GST) | Nos | 25 |
| 11 | SITC of architectural lighting for Stage Step Area (as perapproved designs) High quality floor mounted spot lights , Power: 0.5W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 5º/10º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year. (Quotation Rate Excluding GST) | Nos | 8 |
| 12 | SITC of architectural lighting for Stage & Pedestal Area (as | Nos | 8 |

| | | | |
|---|---|---|---|
| | perapproved designs) High quality floor mounted spot lights , Power: 5W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 5º/10º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year. (Quotation Rate Excluding GST) | | |
| 13 | SITC of architectural Landscape lighting for Stage & Pedestal Area (as perapproved designs) High quality floor mounted spot lights , Power: 5W, CCT : 3000K, Protection Rating : IP65, additional wall mount yoke arrangementsfor fixing the lights. Beam Angle 5º/10º, Body : Die casted/extruded aluminium, Optics. Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Colour: Grey / Black. Warranty 1 year. (Quotation Rate Excluding GST) | Nos | 8 |
| 14 | PVC INSULATED MULTICORE WIRE - SITC of PVC insulated multicore electricalunarmored flexible 3C x 1.5 Sqmm powercablehaving less electrical losses. This PVC insulatedand round sheathed wire features a bright multistrands copper conductors and it supports voltage grade upto 1100V. (As per actuals depending upon the site condition) - polycab /finolex / havells / equivalent (Quotation Rate Excluding GST) | Set | 2 |
| 15 | IP65 T CONNECTORS - SITC of IP65 "T" power connectors easy andextremely precise locking system. High impactmaterials - long-lasting and reliable (Quotation Rate Excluding GST) | Nos | 50 |
| 16 | IP65 I CONNECTOR - SITC of IP65 "I" power connectors having 3/4pole cable connector, chuck type strain relief,Current rating 20Arms continuous, Easy andextremely precise locking system "Quick Lock" High impact materials - long-lasting and reliable (Quotation Rate Excluding GST) | Nos | 50 |
| 17 | ACCESSORIES & ONSITE DETAILING - SITC of additional accessories for installing the lights as per the final drawing/site condition consisting of clamps, brackets, angles, joints, bends, hardwares like fasterners, nut & bolts etc., (Quotation Rate Excluding GST) | Job | 1 |
| 18 | WATERPROOF POWER JUNCTION BOX - SITC of water proof power junction box/ powercable terminal box, IP65 made up of rugged, non-corrosive, high impact polycarbonate, molded nylon encases. connectors that use screw compression tosecure the wires, protection against water jets and dust from all directions, includes 5 Way min 10A connector terminal block Max. dimension :80x250x85mm (Quotation Rate Excluding GST) | Nos | 10 |
| 19 | THEAMATIC LIGHTING DESIGN SERVICES - Architectural Lighting design services for items mentioned in section B (Quotation Rate Excluding GST) | Job | 1 |
| 20 | IP65 DRIVERS 130W Water proof Drivers (Quotation Rate Excluding GST) | Nos | 25 |
| 21 | PACKAGING & HANDLING, LOGISTICS, SCAFOLDING, BOOM LIFT SERVICES, LABOUR SERVICES (Quotation Rate Excluding GST) | Job | 1 |

## Following shall be the calendar events of Tendering: to be read as:

1. Tender Document may be Downloaded from the KPPP Portal of From :11-12-2025, 16.00 Hours
2. Last Date for Uploading the filled Tender Document is 18-12-2025 16.00 Hours.
3. Date of Opening of the quotation is on 19-12-2025 16.30 hours if possible or next working day.

**Terms and Conditions:**

1. The Agency shall quote the rate as per the specification
2. The rate quoted shall be inclusive of all Material, labour, Fabrication, Transportation etc. (Excluding GST)
3. The quotations are invited for the purpose of budgetary offer for adopting rates in estimate.
4. The agencies do not have any claim for entrustment of work
5. Any other information shall be had from the office of the undersigned during office hours
6. BCCC reserves right to accept or reject the quotation part or all without assigning any reason.

Sd/-

Executive Engineer
Shivaji Nagar Division
Bengaluru Central City
Corporation.

**COPY SUBMITTED TO:-**

1. Copy Submitted to the Administrator of BENGALURU CENTRAL CITY CORPORATION - ZONE 2 for kind information.
2. Copy Submitted to the Chief Commissioner, BENGALURU CENTRAL CITY CORPORATION - ZONE 2 for kind information.
3. Copy Submitted to the Special Commissioner for kind information.
4. Copy Submitted to the EIC, BENGALURU CENTRAL CITY CORPORATION - ZONE 2 for kind information.
5. Copy Submitted to the Chief Engineer (QA/QC) for kind information.
6. Copy Submitted to the Superintident Engineer (QA/QC) for kind information.
7. Copy Submitted to the Chief Engineer (West Zone) for kind information.
8. Copy Submitted to the Executive Engineer (Chamarajapete Division) for kind information.
9. Copy Submitted to the Executive Engineer (Gandhinagara Division) for kind information.
10. Copy Submitted to the Executive Engineer (RI-Infra Division) for kind information.
11. Copy to Public Relation Officer BENGALURU CENTRAL CITY CORPORATION - ZONE 2 for information and to publish in two leading Newspapers in Kannada and English.
12. Copy to Additional I.T. Advisor, B.B.M.P. to publish in B.B.M.P. website.
13. Office Copy.

Executive Engineer
Shivaji Nagar Division
Bengaluru Central City
Corporation.